




2013-2015 NTG4.5 GLK-Class

X204

Installation Guide



1. Please power off your original screen before installation.



2. Use a tweezer to rotate the silver ring in a counterclockwise direction.



3. Pry out the side cover of the glove box.



4. Remove the side fixing screws from the air conditioning port.



2013-2015 NTG4.5 GLK-Class

X204

Installation Guide



5. Gently pry and remove the decorative plate.



6. Carefully pry and remove the frame of the OEM screen.



7. Remove the left and right fixing screws of the OEM screen and take out the panel.



8. Loosen the left and right fixing screws of the NTG Unit.



2013-2015 NTG4.5 GLK-Class

X204

Installation Guide



9. Pry out the NTG unit.



10. Disconnect the power harness from the NTG unit and connect it to the Android harness. Please refer to page 7 for the wiring diagram.




11. Assemble the Android stand securely on the dashboard and ensure that the cables are routed properly.



12. Connect all Android cables properly by referring to the provided photo.



2013-2015 NTG4.5 GLK-Class X204 Installation Guide



13. Securely fix and install the Android screen onto the stand.




14. Installation Complete



Microphone Mounting Location

It is recommended to install the microphone at the A-pillar, positioned close to the driver's location.



GPS Antenna Mounting Location

It is recommended to install the GPS antenna on the windscreen, specifically behind the rear-view mirror.



 [dmpcardesign](https://www.instagram.com/dmpcardesign)
 www.dmpcardesign.com
 www.facebook.com/dmpcardesign





2013-2015 NTG4.5 GLK-Class X204 Wiring / Setting Guide




Volume settings

If no sound is heard after the above settings, please check the volume screen and whether the vehicle's fiber optic cable is connected.

- 1) Settings--Volume--Android Volume/OEM Volume
- 2) Settings--Android--Sound




If the car plug has fiber optic plug but without speaker cable, then you need to add a small speaker.



CAN Protocol selection

Settings — Factory (Password 190627) —> Can Protocol : choose 4.0



Note: If the wrong CAN protocol is selected, the display of the air conditioner on the Android screen will not work.




2013-2015 NTG4.5 GLK-Class

X204

Wiring Guide




NTG Installation instructions



Label Recognition:


- Label 1:** NTG 4.0 SWITCH (Short Connect)
- Label 2:** NTG 4.5 SWITCH (Short Connect)
- Label 3:** NTG 4.0/4.5 (CAN Universal Connect)
- Label 4:** NTG 4.5 (Original Car 4.5 CAN Connect)
- Label 5:** NTG 4.0 (Original Car 4.0 CAN Connect)



NTG 4.0

NTG4.0 System Connection:

- Step 1:** Label 3 (NTG4.0/4.5) connect Label 5 (NTG4.0)
- Step 2:** Label 2 (NTG4.5 SWITCH) connect Label 4 (NTG4.5)
- Step 3:** Label 1 (NTG4.0 SWITCH) do not connect




NTG 4.5

NTG4.5 System Connection:

- Step 1:** Label 3 (NTG4.0/4.5) connect Label 4 (NTG4.5)
- Step 2:** Label 1 (NTG4.0 SWITCH) connect Label 5 (NTG4.0)
- Step 3:** Label 2 (NTG4.5 SWITCH) do not connect

Wiring Diagram



Wiring
Diagram